

**BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE**

Office of the Executive Engineer Dasarahalli Division,

No.BBMP/EE/DD/Ten/01/2015-16, Date:04.01.2016

**Indent No.20565****SCHEDULE-B**

**NAME OF WORK:** Reserve fund for Emergency Works( Improvements to prayer ground of Govt. high school near kalasthi nagara in dasarahalli) in Dasarahalli Ward no.15

| Sl. No | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                         | Unit | Qty    | Rates Quoted by Contractor<br><b>N SHIVANANDA</b> |                                                    |              |
|--------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|--------|---------------------------------------------------|----------------------------------------------------|--------------|
|        |                                                                                                                                                                                                                                                                                                                                                                                                                                                             |      |        | In Figures (Rs.)                                  | In Words (Rs.)                                     | Cont. AMOUNT |
| 1      | 2                                                                                                                                                                                                                                                                                                                                                                                                                                                           | 3    | 4      | 5                                                 | 6                                                  | 7            |
| 1      | Earthwork excavation for foundation of buildings, water supply, sanitary, lines and electrical conduits either in pits or in trenches 1.5 m and above in width, in hard soil not exceeding 1.5m. in depth including dressing the bottom and and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead up to 50 m. after breaking of clods complete as per specification & as per direction of Engineer-in-charge | Cum  | 217.08 | 280.0                                             | Rupees Two Hundred Eighty Only                     | 60782.40     |
| 2      | Providing and filling in foundation with granite/ trap broken metal 100m. And down size, with approved sand including hand packing, ramming, watering, including cost of all materials and labour with all lead and lift. complete as per specification & as per direction of Engineer-in-charge                                                                                                                                                            | Cum  | 144.72 | 1988.0                                            | Rupees One Thousand Nine Hundred Eighty Eight Only | 287703.36    |
| 3      | Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220 kgs with 20mm and down size graded granite metal course aggregates @ 0.84 cum and fine aggregates @ 0.56 cum machine mixed, concrete laid in layers not exceeding 15 cms thick, well compacted, in foundation and plinth including cost of all materials, labour HOM of machinery curing complete as per notifications                                            | Cum  | 72.36  | 5100.0                                            | Rupees Five Thousand One Hundred Only              | 369036.00    |




Signature of the Contractor




Executive Engineer

|            |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |       |        |         |                                                |            |
|------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|--------|---------|------------------------------------------------|------------|
| 4          | Cement Concrete Pavement :- Construction of unreinforced, dowel jointed, plain cement concrete pavement over a prepared sub base with 43 grade cement design mix M30 at 360 kg per cum, with 25mm and down size graded granite metal coarse aggregate at 0.69 cum and fine aggregates @ 0.46 cum with superplastizer at 3lts conforming to IS 9103-1999 reaffirmed 2008. coarse and fine aggregate conforming to IS:383, mixed in a batching and mixing plant as per approved mix design, transported to site, laid with a fixed form or slip form paver, spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, dowel bar, tie rod, admixtures as approved, curing, compound, finishing to lines and grades as per drawing complete as per specifications. | Cum   | 72.36  | 6500.0  | Rupees Six Thousand Five Hundred Only          | 470340.00  |
| 5          | Providing T.M.T. steel reinforcement for R.C.C. work including straightening cutting, bending, hooking, placing in position, lapping and (or welding wherever required, trying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | Tonne | 2.53   | 58000.0 | Rupees Fifty Eight Thousand Only               | 146740.00  |
| 6          | Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | Cum   | 217.08 | 83.94   | Rupees Eighty Three and Ninety Four Paise Only | 18221.70   |
| Total      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |       |        |         |                                                | 1352823.46 |
| Percentage |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |       |        |         |                                                | -8.12%     |



Signature of the Contractor

Total 1352823.46  
Percentage -8.12%

  
Executive Engineer,  
Dasarahalli Division,

Signature of the Contractor

Executive Engineer